BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

APPROVED TENDER SCHEDULE –'B'

Name of Work:- Providing and constructing of compound wall in canteen surrounding of Attur ward no-03.

Sl	Description	Unit	Approved Qty	Approved Rate KRIDL	
				Rate	Rate in Words
1	Hire charges of JCB Excavator	Days	1.00	6720.00	Rupees Six Thousand Seven Hundred Twenty Only
2	KSRB 2-1.1 : Earthwork in surface excavation in ordinary soil for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed as per specifications. specification. No. KBS 2.1 (a) / 2.3.1 (P.5/I.2.1 PW, P & IWTD -SR 2016-2017)	Cum	148.73	169.56	Rupees One Hundred Sixty Nine and Paise Fifty Six Only
3	Removing & Refixing Stone Slabs of drains and Pointing in C.M(1:3).	Cum	11.52	82.08	Rupees Eighty Two and Paise Eight Only
4	Providing and fixing Precast RCC Slabs as Per approved design, specification and Direction Engineer-in-Charge. (Approved Data Rate).	Sqm	13.68	2100.00	Rupees Two Thousand One Hundred Only
5	KSRRB M300-53 : Construction of embankment with approved material Gravel/Murrum with all lifts and leads, trasnporting to site, spreading, grading to required slope and compacting to meet requirement Table 300-2 complete as per specifications including cost of gravell/murrum,watering charges & compaction by vibratory roller to 95% of proctors density. MORTH Specification No. 305. (Page No. 147 & Item No. 19.60)	Cum	158.40	311.04	Rupees Three Hundred Eleven and Paise Four Only

Sl	Description	Unit	Approved Qty	Approved Rate KRIDL	
				Rate	Rate in Words
6	KSRB 2-2.2 : Earth work excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5m , in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m. specification, specification. No. KBS 2.1(b) / 2.3.5, No. 5/ Item No. 2.4/(PWD SR 2016-2017)	cum	23.25	305.64	Rupees Three Hundred Five and Paise Sixty Four Only
7	KSRB 4-1.3:Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed,machine mixed,concrete laid in layers not exeeding 15cms.thick, well compacted in foundation,including cost of all materials,labour,HOM of machinery,curing complete as per specifications. Specification no KBS4.1,4.2(Item no 4.3,Page no12,PWD SR 2015-16)	Cum	6.33	5256.36	Rupees Five Thousand Two Hundred Fifty Six and Paise Thirty Six Only
8	KSRB 5.2.3 : Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5.1.13 (Page No. 23/ Item No. 5.6)	Cum	18.44	4521.96	Rupees Four Thousand Five Hundred Twenty One and Paise Ninety Six Only

EXECUTIVE ENGINEER-4
KRIDL, BCMP DIVISION
BENGALURU-560 010

	Description	Unit	Approved Qty	Approved Rate KRIDL	
				Rate	Rate in Words
9	KSRB 5.3-3 : Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.1.13 (P.22/I.5.9 PW, P & IWTD -SR 2016-2017)	Cum	**10.49**	5405.40	Rupees Five Thousand Four Hundred Five and Paise Forty Only
10	KSRB 15.1.5: Providing **flush pointing** to square rubble, course or uncoursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications.(Page No.113/Item No. 15.1)	Sqm	**32.34**	104.76	Rupees One Hundred Four and Paise Seventy Six Only
11	KSRB 4.2.2 : Providing and laying in position Reinforced cement concrete of design mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @0.460cum with superplastesisre @ 3lts conforming etc as per specification&direction of the engineer incharge of work (pwd sr2016-17,p.no13,sno4.11)		**8.18**	6491.88	Rupees Six Thousand Four Hundred Ninety One and Paise Eighty Eight Only
12	KSRB 5-14: Providing and constructing precast concrete solid blocks with compressive strength not less than 35Kg/sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x20x20cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications. (P25/5.27)	Sqm	71.88	1011.96	Rupees One Thousand Eleven and Paise Ninety Six Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Sl	Description	Unit	Approved Qty	Approved Rate KRIDL	
				Rate	Rate in Words
13	Providing 20mm thick cement plaster in single coat with **cement mortar 1:6,** to brick masonry including rounding off corners wherver required smooth rendering, : Providing and removing scaffolding, cost of materials, labour, curing complete as per specifications and direction of the Engineer in charge.for **Outside Plastering(p.no114/item no15.20)**	Sqm	103.50	224.64	Rupees Two Hundred Twenty Four and Paise Sixty Four Only
14	Providingexternalwallswithtextureingapprovedbrandpaint,applieduniformlyinthreecoatsoveronecoatofprimerincludingcostofallmaterials,machineries,labour,transportation,loading &unloading,allleadandliftandotherincidentalchargesincludingscaffoldingandremovingstains,completeasperspecification.(P125/15.103)	Sqm	94.86	311.04	Rupees Three Hundred Eleven and Paise Four Only
15	Providing and fixing pre cast solid cement concrete kerb stones made out of C.C. 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting, including form work, curing, including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc., complete.(pwd sr 2016-17,.n o25 5.30)	Nos	47.00	338.04	Rupees Three Hundred Thirty Eight and Paise Four Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Sl	Description	Unit	Approved Qty	Approved Rate KRIDL	
				Rate	Rate in Words
16	KSRB 14.6-1: Providing and laying heavy duty cobble stones 60mm thick interlock pavers, using cement and course sand for manufacture of blocks of approved size, shape and colour with a minimum compressive strength of 281 kg per sqm over 50mm thick sand bed (average thickness) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand underneath to come up in between joints, final compaction of paver surface joints into its final level, including cost of materials, labour and HOM of machineries complete as per specifications.Specification No. KBS (P.No 101, I.No 14.6)	Sqm	62.90	984.96	Rupees Nine Hundred Eighty Four and Paise Ninety Six Only
17	Fabricating,providing and erecting in position of MS Hot dip galvanized sq.Hallow poles of 132X132 Heavy guage of lenth 3000mm with MS Hot dip galvanized grill work as per approved design and drawing of chief architect.Using 12X75mm galvanized flat for alround frame and 20mmX20mm galvanized forged design with suare for vertical at 150mm c/c as shown in the drawing etc as per specifications and directions of the engineer in charge of the work.(Approved data rate)	Sqm	18.60	12475.03	Rupees Twelve Thousand Four Hundred Seventy Five and Paise Three Only
18	Supplying and fixing M.S. Rectangular Poles made but of 2 equal angles of 65 x 65 x 6 mm welded together and fixed inCC (1:2:4) with 2 Nos. 16 mm dia M. S. hold fast rods each of length 25 cms, including cost of all materials, cutting, bending scafolding etc as per specifications. (P.No 37.2, 255)	Rmtr	14.40	884.52	Rupees Eight Hundred Eighty Four and Paise Fifty Two Only
19	KSRB 7.9 : Providing and fixing M.S.grill work for windows and ventilators weighing 21kg/sqm using M.S. flats, or M.S. square rods, or combination of M.S. flats and square rods as per approved design, drawing including cutting steel sections and weldin (Page No 32, I.No 7.90)	Kgs	81.90	84.24	Rupees Eighty Four and Paise Twenty Four Only

Sl	Description	Unit	Approved Qty	Approved Rate KRIDL	
				Rate	Rate in Words
20	KSRB 15-19.1 : Providing and applying ready mix priming coat over concrete / masonry / asbestos cement sheet / plastered surfaces including preparing the surface after thoroughly cleaning of oil, grease, dirt and other foreign matter, and sand papering including cost of materials, labour, complete as per specifications (Page No 121, Item No 15.80)		6.30	28.08	Rupees Twenty Eight and Paise Eight Only
21	KSRB 15-20.1 : Providing and applying floor painting with ready mix paint in two coats (exluding priming coat) on new concrete / asbestos cement sheet / plastered surfaces brushing to give an even shade after preparing the surface after throughly cleaning oil, dirt, dust other foreign matter and sand papering including cost of materials, labour, complete as per specifications Page No 131, Iem No 15.83)	Sqm	51.30	54.00	Rupees Fifty Four Only
22	Providingd cement concrete pipe NP2 FOR Culverts including pointing ends and fixing collars with cement mortor 1:2 including cost of materials labour curing complete as per specifications 900mm dia (254/34.7.7.2016-2017)	Rmtr	1.80	3924.72	Rupees Three Thousand Nine Hundred Twenty Four and Paise Seventy Two Only
23	Providing and instalation at site of works P.V.C.Pipes including cost of pipes and specials and incluidng lowring into trenches, laying true to line, level and perfect linking at joints, leak proof including jointing encasing the pipe alround to a depth Not less than 15cm with grave or selected earth avalabile from the execavation Etc., Page No.3 item No.4.2 PRE SR2016-2017).	Rmtr	12.00	169.56	Rupees One Hundred Sixty Nine and Paise Fifty Six Only

EXECUTIVE ENGINEER-4
KRIDL, BMP DIVISION
BENGALURU-560 010

Sl	Description	Unit	Approved Qty	Approved Rate KRIDL	
				Rate	Rate in Words
24	Providing and laying/fixing cement base, precast, pre polished cement concrete, designer tiles 25mm thick conforming to IS 1237 heavy duty tiles for flooring, treads of steps and landing, laid on a bed of 12mm thick cement mortar 1:3 mis finished with flush pointing using white cement, including cost of materials, including cutting, griding the edge to half/full round wherever required, labour, curing complete as per specification. P.NO.109.I.NO.14.62	Sqm	9.39	1176.12	Rupees One Thousand One Hundred Seventy Six and Paise Twelve Only
25	KSRRB M100-1 Loading and un loadingofstoneboulder/Stone/aggregates/sand/kanker/Moorum.KSRRB M100-1:Placing tipper at loading point,loading with front end loader, dumping, turning for return trip,excluding time for haulage and return trip complete as per specifications(Item no17.1,Page no 133, PWD SR 2016-17)	Cum	171.97	68.00	Rupees Sixty Eight Only

Signature of the Contractor

KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64

Executive Engineer
Yelahanka Division
Yelahanka Zone
Bruhat Bangalore Mahanagara Palike
BANGALORE 560064